PROJECT NAME:

CAMPBELL SECTION 5

PROJECT LOCATION:

BLOCK 1 SECTION 131 CAMPBELL

DEVELOPER NAME:

JWLAND

DRAWING INDEX

DRG No. DRAWING TITLE

COO1 TITLE SHEET, DRAWING INDEX & LOCALITY PLAN GENERAL NOTES

LANDSCAPE MANAGEMENT AND PROTECTION PLAN

POLLUTION CONTROL PLAN SITE ESTABLISHMENT NOTES & DETAILS

TEMPORARY TRAFFIC MANAGEMENT PLAN 1

DEMOLITION PLAN

BULK EARTHWORKS PLAN

BULK EARTHWORKS SECTIONS 1

BULK EARTHWORKS SECTIONS 2 EXTERNAL SERVICES PLAN

EXTERNAL SERVICES DETAILS

CIVIL WORKS PLAN

CIVIL DETAILS PLAN

C303 LONG SECTIONS

C401 STORMWATER MANAGEMENT PLAN

C501 TURNING DEMONSTRATION PLAN 1

TURNING DEMONSTRATION PLAN 2 TURNING DEMONSTRATION PLAN 3

WASTE MANAGEMENT PLAN





JOB NUMBER:

140778

DISCIPLINE: CIVIL

SUBMISSON TYPE:


WORKS **APPROVAL**





COPYRIGHT ACTmapi 2017

LOCALITY PLAN

GENERAL NOTES **ABBREVIATIONS** THE CONTRACTOR MUST COMPLY WITH THE CURRENT WORK HEALTH AND SAFETY REGULATIONS AND THE ANU AUSTRALIAN NATIONAL UNIVERSITY RELEVANT INDUSTRY CODES AND PRACTICE GUIDELINES BDY BOUNDARY ALL WORK ON ICON WATER SUPPLY AND SEWER MAINS TO BE CARRIED OUT IN ACCORDANCE WITH CURRENT ICON BLDG BUILDING WATER SUPPLY & SEWERAGE STANDARDS RELEASE 2, AMENDMENT 5 SEPTEMBER 2012. ALL WORK ON BARRIER KERB STORMWATER MAINS TO BE CARRIED OUT IN ACCORDANCE WITH DESIGN STANDARDS FOR URBAN INFRASTRUCTURE BKG BARRIER KERB AND GUTTER AND STANDARD SPECIFICATION FOR URBAN INFRASTRUCTURE WORKS. BKT BARRIER KERB - TEMPORARY CONNECTIONS AND OR DISCONNECTIONS OF SEWER AND WATER AT THE MAIN TO BE MADE BY ICON WATER AT CONSTRUCTION JOINT CONTRACTOR'S EXPENSE. THE CONTRACTOR IS TO EXPOSE THE MAIN AT THE LOCATION OF THE COVER LEVEL CONNECTION/DISCONNECTION IN PREPARATION FOR THE WORK BY ICON WATER. ALL EXCAVATION IN THE VICINITY CTB CONCRETE THRUST BLOCK OF MAINS IS TO BE CARRIED OUT BY HAND. DIMENSION ALTHOUGH THE POSITIONS OF EXISTING UNDERGROUND SERVICES HAVE BEEN PLOTTED FROM AVAILABLE RECORDS, DSN DESIGN THE CONTRACTOR SHALL CONFIRM THE DEPTH AND LOCATION OF ALL SERVICES ON SITE BEFORE COMMENCING DEVELOPMENT, REVIEW AND COORDINATION EXCAVATIONS. CONTRACTOR TO ADVISE DESIGN ENGINEER IF NOT IN ACCORDANCE WITH THE PLAN. DRIVEWAY DWY ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (AHD) **EXPANSION JOINT** ALL COORDINATES ARE BASED ON THE CANBERRA LOCAL GRID SYSTEM. FLUSH KERB THE CONTRACTOR MUST SECURE ALL PERMITS, ARRANGE ALL CLEARANCES AND PAY ALL FEES REQUIRED TO GRATED DRAIN COMPLETE THE PROJECT BEFORE COMMENCING WORK. HYDRANT WORK AS EXECUTED DRAWINGS, TIE BOOK AND DEPOSITED PLAN MUST BE SUBMITTED BEFORE CONNECTION. HEAVY DUTY ANY NON-METALLIC WATER SERVICE IS TO BE INSTALLED WITH TRACER WIRE AND TESTED. HIGH END RISER 10. EXCESS EXCAVATED MATERIAL SHALL BE REMOVED FROM SITE AND DISPOSED OF AT AN APPROVED SPOIL AREA. INVERT LEVEL THE CONTRACTOR SHALL REINSTATE ALL DISTURBED SURFACES TO MATCH EXISTING. INTERMEDIATE RISER 12. THE CONTRACTOR IS RESPONSIBLE FOR THE PREPARATION OF ALL NECESSARY TEMPORARY TRAFFIC MANAGEMENT KERB AND GUTTER PLANS AND THEIR APPROVAL IN ACCORDANCE WITH AS1742.3 KEY JOINT 11. THE CONTRACTOR IS RESPONSIBLE FOR THE PREPARATION OF ALL NECESSARY POLLUTION CONTROL PLANS AND KERB ONLY THEIR APPROVAL. MANHOLE 12. SURFACES WHICH LIE OUTSIDE THE GENERAL LIMIT OF LANDSCAPING AND RESTORATION WHICH ARE DISTURBED MOUNTABLE KERB DURING THE CONSTRUCTION OF THE WORKS. SHALL BE RESTORED BY THE CONTRACTOR AT THE CONTRACTORS MOUNTABLE KERB AND GUTTER EXPENSE TO AT LEAST THEIR PRE-CONSTRUCTION CONDITION MOUNTABLE KERB TIED 13. USE FIGURED DIMENSIONS – DO NOT SCALE MLBK MODIFIED LAYBACK KERB 14. MAKE SMOOTH CONNECTION TO EXISTING WORK MOWING STRIP ALL CONSTRUCTION WORKS SHALL BE COORDINATED WITH ADJACENT CONTRACTS OPEN CHANNEL INVERT 16. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE CONTRACT DOCUMENTS PVC-U UNPLASTICISED POLYVINYL CHLORIDE 17. THE CONTRACTOR MUST MAKE ALLOWANCES FOR ALL TOPOGRAPHIC CONSTRAINTS AFFECTING THE EXECUTION OF PRAM CROSSING THE WORKS AND THE RESTORATION OF THE SITE. PRAM RAMP 18. SERVICES INDICATED ON THESE PLANS WERE COMPILED FROM PLANS RECEIVED FROM THE UTILITY COMPANIES REDUCED LEVEL THROUGH THE DIAL BEFORE YOU DIG NETWORK ROCI REINFORCED OPEN CHANNEL INVERT 19. THE LOCATION OF SOME EXISTING UTILITIES ARE SHOWN IN THEIR APPROXIMATE LOCATION ONLY. PRIOR TO ANY RVC REINFORCED VEHICULAR CROSSING DEMOLITION, EXCAVATION OR CONSTRUCTION ON SITE, THE CONTRACTOR SHALL CONTACT THE RELEVANT SUBSOIL DRAIN AUTHORITIES AND VERIFY THE LOCATION OF ALL UNDERGROUND SERVICES ON THE SITE AND OBTAIN ALL STOP VALVE NECESSARY CLEARANCES TCCS TRANSPORT CANBERRA AND CITY SERVICES 20. ALL DESIGN SUBGRADE VALUES MUST BE CONFIRMED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF TOOLED JOINT PAVEMENT CONSTRUCTION VEHICULAR CROSSING 21. PROPERTY BOUNDARIES SHOWN ON DRAWINGS ARE TAKEN FROM SUPPLIED CADASTRAL MAPPING AND/OR WEAKENED PLANE JOINT SURVEYED BOUNDARIES SAFETY IN DESIGN CONSTRUCTION PHASE: • THE CONTRACTOR MUST COMPLY WITH THE CURRENT WORK HEALTH AND SAFETY LAWS. THE RELEVANT WHS REGULATIONS AND THE RELEVANT INDUSTRY CODES AND PRACTICES GUIDELINES. • AVOID THE USE OF HEAVY MACHINERY OR HEAVY VIBRATING LOADS NEAR LARGE TRUNK GAS, WATER SUPPLY AND COMMUNICATIONS INFRASTRUCTURE WITHIN THIS SITE. • ALL WORKS MUST BE UNDERTAKEN WITH APPROVED TTM PLANS AND IN ACCORDANCE WITH AS1742.3 NO WORK IS TO BE UNDERTAKEN IN POOR VISIBILITY CONDITIONS (BAD WEATHER, FOG, SUN GLARE, DARKNESS ETC) PHYSICALLY IDENTIFY ALL EXISTING SERVICES ON SITE BEFORE COMMENCING ANY EXCAVATIONS KEEP CLEAR OF EXISTING OVERHEAD LINES MAINTENANCE PHASE: • AVOID THE USE OF HEAVY MACHINERY OR HEAVY VIBRATING LOADS NEAR LARGE TRUNK GAS. WATER SUPPLY AND COMMUNICATIONS INFRASTRUCTURE WITHIN THIS SITE. • ALL MAINTENANCE WORK IS TO BE UNDERTAKEN WITH APPROVED TTM PLANS AND IN ACCORDANCE WITH AS1742.3 NO MAINTENANCE IS TO BE UNDERTAKEN IN POOR VISIBILITY CONDITIONS (BAD WEATHER, FOG, SUN GLARE, DARKNESS ETC). PHYSICALLY IDENTIFY ALL EXISTING SERVICES ON SITE BEFORE COMMENCING ANY EXCAVATIONS KEEP CLEAR OF EXISTING OVERHEAD LINES **CONSTRUCTION PHASE:** • THE CONTRACTOR MUST COMPLY WITH THE CURRENT WORK HEALTH AND SAFETY LAWS, THE RELEVANT WHS REGULATIONS AND THE RELEVANT INDUSTRY CODES AND PRACTICES GUIDELINES. AVOID THE USE OF HEAVY MACHINERY OR HEAVY VIBRATING LOADS NEAR LARGE TRUNK GAS, WATER SUPPLY AND COMMUNICATIONS INFRASTRUCTURE WITHIN THIS SITE. • ALL WORKS MUST BE UNDERTAKEN WITH APPROVED ENVIRONMENTAL PLANS/TTM PLANS AND IN ACCORDANCE WITH AS1742.3 NO WORK IS TO BE UNDERTAKEN IN POOR VISIBILITY CONDITIONS (BAD WEATHER, FOG. SUN GLARE, DARKNESS ETC) PHYSICALLY IDENTIFY ALL EXISTING SERVICES ON SITE BEFORE COMMENCING ANY EXCAVATIONS KEEP CLEAR OF EXISTING OVERHEAD LINES DESIGN REFERENCES FOR FOOTPATH CONSTRUCTION REQUIREMENTS REFER TCCS STANDARD DRAWING DS13-01 (PATH STANDARD DETAILS) FOR KERB DETAILS REFER TCCS STANDARD DRAWING DS3-01 (KERB AND GUTTER STANDARD DETAILS SHEET 1) FOR PRAM CROSSING, PRAM RAMP AND VEHICULAR CROSSING DETAILS REFER TCCS STANDARD DRAWING DS3-02 (KERB AND GUTTER STANDARD DETAILS SHEET 2) FOR DOMESTIC DRIVEWAY DETAILS REFER TCCS STANDARD DRAWING DS5-01 (DOMESTIC DRIVEWAYS), FOR HEAVY DUTY DRIVEWAY DETAILS REFER TCCS STANDARD DRAWING DS5-02 (HEAVY DUTY DRIVEWAYS) DRAWING TITLE DESIGNED BY CHASE FRONT ARCHITECTS MIXED USE DEVELOPMENT GENERAL NOTES NOT TO SCALE sellick consultants CHECKED BY CAMPBELL 5 STRUCTURAL CIVIL HYDRAULIC AUTHORISED BY PROJECT LOCATION DRAWING NO. | REV. DO NOT SCALE OFF DRAWINGS canberra sydney brisbane BLOCK 1 SECTION 131 VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. 05.09.17 DA FOR WORKS APPROVAL C003 B COPYRIGHT: The concepts and information contained in this document are copyright of Sellick DATE 02 6201 0200 www.sellickconsultants.com.au FOR REVIEW 24.08.17 DA CAMPBELL, ACT Consultants. Use or copying of this document in whole or in part without written permission constitutes 05/09/2017 ISSUE DESCRIPTION DATE DRAWN







05.09.17 DA

24.08.17 DA

DATE DRAWN

FOR WORKS APPROVAL

FOR REVIEW

ISSUE DESCRIPTION

CONTACT DETAILS

PROJECT MANAGER: CHASE BUILDING GROUP ACT
SITE MANAGER: CHASE BUILDING GROUP ACT

HOURS OF OPERATION

SITE WORKS TO BE CONDUCTED $\underline{\mathsf{ONLY}}$ BETWEEN THE FOLLOWING HOURS:

- WEEKDAYS 7.00AM TO 6.00PM;
- SATURDAYS 7.00AM TO 6.00PM
- SUNDAYS BUILDING WORK MUST NOT EXCEED NOISE STANDARD

WASTE NOTES

1. WASTE ENCLOSURE(S) ARE TO BE USED FOR ALL RUBBISH
ON SITE AND RUBBISH REMOVED FROM ENCLOSURE(S) WHEN

REQUIRED OR FULL. CUT AND FILL VOLUMES

CUT 63,414m³

FILL Om³

EXCESS SOIL TO BE DISPOSED OF AT AN ENVIRONMENT PROTECTION AUTHORITY APPROVED LOCATION.

NOISE

ENSURE ALL BUILDING WORK THAT GENERATES NOISE IS
CONDUCTED WITHIN THE TIME PERIODS DETAILED IN SCHEDULE 2
OF THE ENVIRONMENT PROTECTION REGULATIONS 2005.

BUILDING WORK DETAILS	MONDAY TO SATURDAY	SUNDAY AND PUBLIC HOLIDAYS		
INDUSTRIAL, CITY AND TOWN CENTRE AREAS	6AM TO 8PM	6AM TO 8PM		
ANY OTHER AREA WHEN WORK COMPLETED WITHIN 2 WEEKS	7AM TO 6PM	8AM TO 8PM		
ANY OTHER AREA WHEN WORK NOT COMPLETED WITHIN 2 WEEKS	7AM TO 6PM	BUILDING WORK MUST NOT EXCEED NOISE STANDARD		

IN ADDITION:

- SCHEDULE NOISY ACTIVITIES FOR THE LEAST
 SENSITIVE TIMES OF THE DAY SUCH AS MID-MORNING
 AND MID-AFTERNOON.
- 2. SELECT MACHINERY THAT PRODUCE LESS NOISE; AND
- ENSURE MACHINERY IS WELL MAINTAINED.

SEDIMENT CONTROL POND NOTES

- 1. DISCHARGE FROM THE POND IS PERMISSIBLE WHEN THE WATER pH IS 6.5-8.5 AND IS CLARIFIED TO OR AT BELOW 60mg/L (50NTU). IF SEDIMENT LEVEL IS GREATER, THEN PRIOR TO DISCHARGE, THE DAM MUST BE DOSED WITH EITHER ALUM OR GYPSUM AND ALLOWED TO SETTLE UNTIL THE SEDIMENT IS LESS THAN 60mg/L (50NTU).
- WATER LEVEL TO BE MAINTAINED AT LESS THAN 20% OF CAPACITY TO ALLOW RUNOFF STORAGE DURING A RAIN EVENT.
 REGULAR DREDGING OF THE DAM MUST BE CARRIED OUT TO
- 4. SITE DRAWING AND DETAILS MUST BE PROVIDED TO ENVIRONMENT PROTECTION AUTHORITY, FOR APPROVAL PRIOR TO WORKS COMMENCING.

NOTE

REMOVE SILT.

ALL WORK IS TO COMPLY WITH ENVIRONMENT
PROTECTION GUIDELINES FOR CONSTRUCTION AND
LAND DEVELOPMENT IN THE ACT 2011

SEDIMENT CONTROL NOTES

- 1. SEDIMENT AND EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH "ENVIRONMENT PROTECTION GUIDELINES FOR CONSTRUCTION AND LAND DEVELOPMENT IN THE ACT" (ENVIRONMENT PROTECTION AUTHORITY MARCH 2011) AND FULLY OPERATIONAL PRIOR TO STRIPPING OF SITE TOP SOIL.
- . STOCK PILE/S TO BE LOCATED AWAY FROM DRAINAGE LINES AND SURFACE FLOW PATHS.
- CONTOURED STRIATIONS OR FURROWS TO BE PROVIDED TO STOCK PILES TO MINIMISE EROSION. STABILISED CONSTRUCTION ENTRANCE TO BE CONSTRUCTED PRIOR TO ACCESS TO SITE BY
- CONSTRUCTION VEHICLES. AGGREGATE TO BE TURNED WHEN SEDIMENT BUILDS UP AND RENEWED WHEN REQUIRED.
- 4. WHERE UNDERGROUND STORMWATER DRAINAGE IS INSTALLED TO INTERNAL ROADWORKS, PROVIDE INLET FILTER IN ACCORDANCE WITH GIVEN DETAIL.
- 5. AVERAGE EXISTING SITE SLOPE: 2.9%
- TOTAL SITE AREA: 5,720m²

 ENVIRONMENT PROTECTION AGREEMENT TO BE TAKEN OUT BY BUILDING CONTRACTOR WITH ENVIRONMENT PROTECTION AUTHORITY. (TELEPHONE 132281)
- 8. ALL NEW CONSTRUCTION WORK MUST BE CONTAINED WITHIN THE SITE EXCEPT FOR APPROVED
- SERVICE CONNECTIONS AND ROADWORKS.

 9. LIMIT ACCESS TO SITE DURING AND IMMEDIATELY AFTER WET WEATHER.
- 10. REGULARLY REMOVE ANY SOIL FROM ROADS ADJACENT TO THE SITE.11. NO STORAGE OF CONSTRUCTION MATERIALS, PARKING OF VEHICLES NOR EQUIPMENT PERMITTED
- OUTSIDE OF BLOCK WITHOUT Tams APPROVAL.

 12. NO SITE SHEDS, STORAGE SHEDS OR SITE AMENITIES TO BE ERECTED OUTSIDE OF BLOCK
- WITHOUT Tams Approval.

 13. PROVIDE KERBSIDE FILTER ROLL TO EXISTING SUMPS WHERE INDICATED, REFER TO GIVEN
- DETAIL.

 14. KERBSIDE FILTER ROLLS TO BE REMOVED, CLEANED AND REINSTATED ON A WEEKLY BASIS AT A MINIMUM. TRAPPED SEDIMENT ABOUT SUMPS ALSO TO BE REMOVED. CLEANING IS ALSO TO
- TAKE PLACE IMMEDIATELY AFTER PERIODS OF RAINFALL DURING CONSTRUCTION.

 15. ALL SERVICE TRENCHES TO BE BACK FILLED WITHIN 24 HOURS OF INSPECTION.
- 16. EXCESS SOIL IS TO BE DISPOSED AT AN ENVIRONMENT PROTECTION AUTHORITY APPROVED
- 17. THE SITE FOREMAN IS TO CONTACT THE ENVIRONMENT PROTECTION AUTHORITY (132281) TO ARRANGE A SITE INSPECTION AND ENDORSEMENT OF SEDIMENT AND EROSION CONTROL MEASURES PRIOR TO WORKS COMMENCING.
- 18. THE SITE FOREMAN IS TO CONTACT THE ENVIRONMENT PROTECTION AUTHORITY (132281) TO DISCUSS ANY PROPOSED MAJOR CHANGES TO SEDIMENT AND EROSION CONTROLS ON SITE PRIOR TO IMPLEMENTING THE CHANGES.
- 19. THE SITE FOREMAN IS TO ENSURE CONTRACTOR'S ACCESS AND EXIT THE SITE USING ONLY ENVIRONMENT PROTECTION AUTHORITY APPROVED STABILISED ACCESS/EXIT POINTS AS DETAILED ON ENDORSED SEDIMENT AND EROSION CONTROL PLANS.

MAINTENANCE SCHEDULE

WEEKLY:

CHECK AND REINSTATE SILT CONTROL FENCES.

DAILY:

SWEEP AND REMOVE DIRT AND ANY OTHER BUILDING MATERIAL FROM GUTTERS, FOOTPATHS AND ROADWAYS ADJACENT TO THE SITE BY CLOSE OF BUSINESS AND PRIOR TO RAIN AND AS REQUIRED. ALL NECESSARY STEPS SHOULD BE TAKEN THAT ARE PRACTICAL AND REASONABLE TO MINIMISE DUST POLLUTION.

DURING/AFTER WET WEATHER:

LIMIT CONSTRUCTION VEHICLE ACCESS TO SITE DURING AND IMMEDIATELY FOLLOWING WET WEATHER CHECK AND REINSTATE SEDIMENT EROSION CONTROL MEASURES AND CHECK ROAD.

DUST MANAGEMENT

WHERE BUILDING WORK GENERATES DUST, ALL REASONABLE AND PRACTICABLE MEASURES SHOULD BE TAKEN TO MINIMISE THAT DUST.

THIS CAN OFTEN BE ACHIEVED BY

1. RETAINING EXISTING VEGETATION WHERE POSSIBLE

- 2. STRIPPING AREAS PROGRESSIVELY AND ONLY WHERE IT IS NECESSARY FOR WORKS TO OCCUR
- . EMPLOYING STABILISING METHODS SUCH AS MATTING, GRASSING OR MULCH
- 4. DAMPENING THE GROUND WITH A LIGHT WATER SPRAY (CONTACT THE ENVIRONMENT PROTECTION AUTHORITY FOR REQUIREMENTS DURING EXTREME DROUGHT CONDITIONS)
- 5. ROUGHENING SURFACE OF EXPOSED SOIL

 6. COVERING STOCKPILES AND LOCATING THEM WHERE THEY ARE PROTECTED FROM THI
- . COVERING STOCKPILES AND LOCATING THEM WHERE THEY ARE PROTECTED FROM THE
- 7. RESTRICTING VEHICLE MOVEMENTS
- COVERING THE LOAD WHEN TRANSPORTING MATERIAL
- CONSTRUCTING WIND BREAKS SUCH AS WIND FENCES IN ACCORDANCE WITH THE BLUE BOOK
- A WATER CART OR SUFFICIENT WATER SPRAYS SHALL BE MADE AVAILABLE AT ALL TIMES. IN ADVERSE CONDITIONS WHEN DUST CANNOT BE ADEQUATELY CONTROLLED WHEN WORKS ARE BEING UNDERTAKEN, WORKS WILL CEASE IN THESE AREAS UNTIL CONDITIONS IMPROVE;
 - WATER SHALL BE APPLIED TO SUPPRESS DUST FROM OPEN EARTHWORKS AS WELL AS UNPROTECTED STOCKPILES
- 2. AREAS OF COMPLETED EARTHWORKS SHALL BE PROGRESSIVELY REHABILITATED WITH DRYLAND GRASS AND FENCED OFF AS SOON AS PRACTICABLE TO PREVENT FURTHER EROSION
- 13. THE CONTRACTOR SHALL CONTACT ICON WATER TO OBTAIN RECYCLED WATER FROM THE LOWER MOLONGLO
- 14. THE CONTRACTOR IS TO CONTACT THE WATER RESOURCES UNIT TO OBTAIN AN EXEMPTION TO USE NON-POTABLE WATER FROM ON OR OFF THE SITE IF REQUIRED

DISPOSAL OF SPOIL

PRIOR TO ANY WORKS COMMENCING INVOLVING EXPORT OF SPOIL GREATER THAN 100m³, THE FOLLOWING INFORMATION MUST BE PROVIDED TO THE ENVIRONMENT PROTECTION AUTHORITY VIA EMAIL (environment.protection@act.gov.au):

- 1. WHERE THE SPOIL WILL ORIGINATE FROM: WHO IS DISPOSING OF THE SPOIL: WHERE THE SPOIL WILL BE TAKEN: THE AMOUNT OF SPOIL TO BE TAKEN AWAY
- 2. MOVEMENT DATES AND CONTACT DETAILS: DESCRIPTION OF THE TYPE OF SPOIL TAKEN AWAY:DETAILS OF HOW RECORDS WILL BE KEPT; AND
- 3. TIME FRAME TO COMPLETE THE WORKS TO THE SATISFACTION OF THE ENVIRONMENT

PROTECTION AUTHORITY.

SPOIL MAY BE TAKEN TO AN APPROVED LANDFILL SITE WITHOUT APPROVAL. IF THE SPOIL IS TO BE TAKEN TO AN AREA OTHER THAN APPROVED LANDFILL SITE, ENSURE THE ACCEPTOR OF THE SPOIL IS AWARE OF THE REQUIREMENTS SETOUT IN SECTION 8.2 OF THE ENVIRONMENT PROTECTION GUIDELINES FOR CONSTRUCTION AND LAND DEVELOPMENT IN THE ACT.

FIRE

BURNING OF WASTE MATERIALS ON THE SITE, SUCH AS PLASTICS, CHEMICALS OR WOOD THAT MAY BE PAINTED, CHEMICALLY TREATED OR CONTAMINATED WITH CHEMICALS IS ILLEGAL. A FIRE MAY BE PERMITTED FOR HEATING PURPOSES PROVIDED IT IS IN A BRAZIER OR CONSTRUCTED FIREPLACE. ONLY SEASONED, UNTREATED TIMBER CAN BE BURNED FOR HEATING PURPOSES.



PROJECT TITLE	DESIGNED BY	DRAWING TITLE	SCALE		
MIXED USE DEVELOPMENT	AM	SITE ESTABLISHMENT			
CAMPBELL 5	CHECKED BY	NOTES & DETAILS			
CAMPOLLE	CO	NOILS & DLIAILS			
DO NOT SCALE OFF DRAWINGS	AUTHORISED BY	PROJECT LOCATION	JOB NO.	DRAWING NO.	REV.
VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK.		BLOCK 1 SECTION 131	1/ 0770	C407	D
COPYRIGHT: The concepts and information contained in this document are copyright of Sellick Consultants. Use or copying of this document in whole or in part without written permission constitutes	DATE	CAMPBELL. ACT	140778	C103	D
an infringement of copyright.	05/09/2017	CALIL DELE, ACT	I	1 1	I

